



THE HOUSING AUTHORITY OF GLOUCESTER COUNTY

Addendum No. 1

Re: Repair and Sealcoating of Asphalt Paving @ Carino Park Apartments
Project: IFB 17-009
Date: 3.20.2017

Clarifications as a result of Pre-Bid Conference:

1. Paved Areas to be patched with HMA due to alligator or uneven conditions consist of:

13 Locations with an overall square footage of 1383 SF.

This does not include the isolated cracks which are in addition to the areas noted above and are required to be filled as specified.

Contractor to submit a unit price for additional patch repair should new areas be required.

2. Paved area along penetrated wheel stops at Southwest edge of parking lot to be cleaned by HAGC prior to sealcoating.

3. Sealcoat product to be Coal Tar as per SealMaster Coal Tar Concentrate Pavement Sealer or equal.
(See attached product description for mixing procedure and application)

